



SECONDARY PULL BOX FOR STREET LIGHTING

NOTES:

1. COVER TO BE MARKED "STREET LIGHTING"
2. CONDUITS IN PULL BOX SHALL NOT BE TRANSPOSED. THE LAST 8" OF EACH CONDUIT SHALL BE STRAIGHT AND SO PLACED THAT THE PROLONGATION OF THE 8" LENGTH SHALL PASS THROUGH THE COVER OPENING.
3. THE BONDING JUMPER SHALL BE CONNECTED TO ALL RIGID CONDUIT IN PULL BOX
4. TOP OF PULL BOX TO BE LEVEL WITH SIDEWALK WHEN INSTALLED IN SIDEWALK
5. TOP OF PULL BOX TO BE 1" ABOVE GRADE WHEN INSTALLED IN PARKWAY. THE GRADE SHALL BE A STRAIGHT LINE FROM THE TOP OF THE BACK FACE OF CURB TO THE NEAR EDGE OF SIDEWALK



REVISION APPROVED

GEN. Supt./CHIEF ENGR.

LATEST REVISION: DELETED CONCRETE FLOOR,
CHANGED SIZE BOND WIRE.

UGS-311